

## UPCOMING EVERSOURCE CONSTRUCTION 2018-19

Eversource is replacing transmission structures in Derry, Auburn, Chester, Raymond, Candia, Deerfield, Northwood, Strafford and Rochester. This project is one of several that are designed to improve the reliability of the electric system serving New Hampshire. Starting in June 2018, Eversource's contractors PAR Electrical Contractors, BluRoc LLC, JCR Utility Construction Co., Michels Power, and Three Phase Line Construction will be replacing existing wood transmission structures with steel structures of similar size and height. This work will take place within the transmission power line corridor from Derry to Rochester.

### Here is important information about how we will work in your neighborhood:

- **Reliable Service:** Be assured that this work will not interrupt electric service to your property.
- **Proper Identification:** All people working on this project carry identification.
- **Where We'll Be Working Nearby:**
  - o **Raymond:** Lane Road, Power Street, Route 27, Critchett Road
  - o **Candia:** Green Road, Route 101, Depot Road, Critchett Road
  - o **Deerfield:** Mountain Road, Nottingham Road
  - o **Northwood:** Lucas Pond Road, Route 4, Rochester Road
- **Communication:** Keeping the lines of communication open is important to us. Before work starts, our field outreach representatives will be in touch, either in person or with a door hanger notice to provide more details about the construction schedule for your area. We will also provide updates to keep you informed of our work. **In the meantime, feel free to reach out to us by calling 1-888-926-5334 or emailing at NHProjectsInfo@eversource.com if you have any questions.**
- **Construction Days:** Construction will be Monday-Friday, some Saturdays. Please keep in mind that the schedule may change due to weather and other unexpected circumstances.

### • CONSTRUCTION ACTIVITIES:

- IN THE COMING WEEKS:** Crews will prepare access points and work sites for the equipment installations. This may require site grading, mowing/vegetation removal, and adding gravel to the access road.
- IN THE COMING MONTHS:** Crews will replace existing wood structures with weathering steel structures, steel poles with a finish that "weathers" or darkens over time. To facilitate the installation of the new structures, the crews may first drill foundations with the use of a drill rig. When required, drilling activities usually take place for a few days, depending on soil conditions.
- OVERALL, you can expect:** – There will be construction vehicles on the right of way, though we will make every effort to minimize any impact to your property.
  - In wetland areas, we may install timber mats, which are flat surfaces to protect an area from construction activities and equipment; they will be removed at the end of the project.
  - Restoration, if needed, will take place when the project is complete.
- PROJECT COMPLETION:** We expect to complete the project and do final restoration of disturbed areas by the Spring of 2019.

**Again, if you have questions about this project or the hours of construction, please call 1-888-926-5334 or email us at NHProjectsInfo@eversource.com. Thank you.**